

RAPID RUN PARK

Under Construction

Construction: Fall 2013 - Fall 2014



Project Description: About 1,600 linear feet of bioswale will be constructed on the park grounds parallel to Rapid Run Pike. The bioswale will carry stormwater runoff from the park, Rapid Run Pike and the hillsides/grounds on the south side of Rapid Run Pike, including the CRC playground and ballfield.

Stormwater sewers will be constructed along the project route to carry stormwater to the bioswale and under the park's parking lot.

Two small bioretention basins on the south side of Rapid Run Pike will also collect stormwater for the bioswale.



PROJECT GROUNDWORK
your pipeline to clean water

METROPOLITAN
SEWER DISTRICT
of greater
CINCINNATI

